


# CITY OF LAKEPORT

*Over 100 years of community,  
pride, progress, and service*



## CITY OF LAKEPORT

### ADDENDUM NO. 4 LIBRARY PARK SEAWALL REPLACEMENT PROJECT Bid No. 19-01

Issued Date: October 28, 2019

The bid date has been changed to November 4, 2019 at 2 PM in the City Hall front conference room.

The following questions were asked and attached are the answers:

1. Question: Is the SLZ 14-770 cold rolled pile an acceptable alternate to the AZ 14-770?  
Answer: Yes
2. Question: Can a bolt be placed back and left in each hole at end of project for temporary holes drilled in piling temporary pile capping systems?  
Answer: No. Clarification: No holes shall be drilled into the piles which will be left exposed after installation of the concrete pile cap. The specifications allow for welding temporary studs or supports to the sheet piles. Any temporary fixtures or fittings shall be removed and ground flush prior to the completion of the pile cap. Fittings or fixtures on the land side of the wall below the level of the sidewalk and aggregate base (approximately 16 inches) from the bottom of the concrete pile cap shall be cut off but need not be ground flush.

Please indicate receipt of this addendum on the proposal at the location indicated. Failure to do so may cause rejection of your bid.

Approved:

Paul Curren  
City Engineer